



**Building Preparation Manual
Standard Style Concrete Frame
Inside Mount**

July 2017

SAFETY You are responsible for the safe use of this product. Unsafe use could result in property damage, serious personal injury, serious injury to others or a fatality.

Do not operate the door until you understand all the safety instructions. If you have any questions, contact your door provider or go to www.powerliftdoors.com for assistance.

Recognize safety information and labels:

- The labels are located on the pump and at eye level at each door frame jamb.
- Understand the label's meaning and the potential risk it identifies
- Follow all information on the label
- Keep the labels in good condition
- Replace unreadable labels by contacting:
your door installer or www.powerliftdoors.com

Follow all safety instructions:

- Read and understand all safety, operation and maintenance instructions
- Allow only those persons who have read and understand the instructions to operate the door
- Turn off power when making electrical connections or conducting any electrical work
- Install all electrical connections per state and local codes
- Do not re-adjust or modify the settings completed by the door installer
- Avoid electrical shock by not operating controls with wet hands or standing on a wet surface
- Operate the door only for the door's intended purpose
- Inspect and verify that the area in the path of the door swing is free of equipment, vehicles or obstructions.
- Stay alert and watch during the door's operation
- Keep fingers and extremities away from pinch points located between the door and door frame
- Keep children and pets away from the door while door is operating
- Maintain the door in good operating condition
- Wear safety glasses when using hydraulic connections
- If a remote control is ordered, do not leave the remote transmitter where unauthorized persons could operate the control
- If cane bolts are provided, verify the bolts are not engaged prior to door operation

Maintenance

Yearly inspect hoses, lines and connectors for signs of deterioration. Contact your door installer if deterioration is detected.

In high moisture buildings, (dairy buildings, livestock confinements) replace the hydraulic oil to prevent moisture accumulation. Protect motor from excessive moisture.

Installation Instructions for Concrete Framing (Inside Mount)

PowerLift Hydraulic Doors is delighted to be providing our product on your project. We look forward to working with you and arranging for a quick and trouble-free installation. All PowerLift Hydraulic Doors will only be installed by our company representatives. By cooperating together we can provide an expedited project schedule. Several procedures should be completed for a trouble free installation.

Prior to door fabrication and installation:

The rough opening should be completed with the side columns plumb, straight and the header level, straight and without bow or twist. To eliminate any building movement, installation of roof trusses, wall girts, bracing and roof sheathing should be concluded. (Review Suggested Framing Recommendations)

The project must have drivable access to the project site and door rough opening.

Door installation is preferred to be completed prior to concrete floor placement. By allowing our door frame posts to extend and the concrete placed around them, the post are soundly secured. For completed concrete floors, the PowerLift door installer will install anchor bolts and anchor plates.

Door side jamb trim installed prior to door installation. This method is quicker and less problematic for the builder than installing the trim after the door is installed.

PowerLift hydraulic doors fasten to the inside of the header. Bracing should not extend closer than 3" from the bottom of the header opening. (See Header Detail drawing)

The door purchaser is responsible to provide a telehandler, or other acceptable equipment capable of lifting the door from the trailer and carrying the door to the building opening.

Four to five gallons of hydraulic oil, compatible to the Owner's equipment, available for pump installation. ISO 32 hydraulic oil is recommended.

Permanent electrical power is not required for the door installation. However, a 220v and 30 amp breaker is required for permanent door operation.

Door arrival:

The door will arrive on a trailer pulled by our delivery truck with at least one door installer. The door and frame will arrive as one painted component. All horizontal wood/steel girts, cylinders and hydraulic lines will be installed with the door.

The door will be moved from the trailer to the door rough opening with the help of the contractor supplied equipment. The PowerLift Installer, will then position, adjust and fasten the door to the building. Fastening is completed in two stages. First stage is by installing long concrete bolts through door frame legs into the side concrete of the building. The second stage is by installing concrete bolts through the header mounting angle into the

building header. (See Typical Header Detail and Typical Concrete Building Side Jamb Detail drawings).

Upon completion of securing the door, the hydraulic pump and connecting hydraulic hoses will be installed on the designated door side. The pump is fastened to framing members by either concrete bolts or a steel plate welded to the door frame post. If the pump requires to be removed (for the example, for lining the building interior) concrete bolts of the same diameter but of longer length can be used. The height of the pump controls should be located at 72" off finished floor. This discourages young or unauthorized individuals from operating the door.

The Powerlift Installer will connect temporary power and pour the hydraulic oil (supplied by others) into the pump reservoir. The door will be temporarily operated through several cycles. Any final adjustments will be completed prior to the installer leaving the project. If the Owner is available, operating instructions will be provided by the installer.

A rubber membrane is provided as a weatherstripping to cover the hinges at the top of the door. The weatherstripping is fastened prior to door cladding installation. The weatherstripping should be placed on the building behind the steel above the door, approximately 2" in height. The weatherstripping will lay across the hinges, and be fastened to the door. Care should be taken to remove wrinkles and provide a smooth neat appearance when installing the weatherstripping. The weatherstripping is fastened on the outside of the door cladding. In the case of steel panels, fasten the weatherstripping with screws in every raised rib location through the J-channel. (See Typical Header Detail drawing) Any door trim and cladding must be sealed with a good quality sealant to prevent moisture from penetrating the door envelope.

Inspect the door to verify that the vertical margins are equal between the door and the building jambs. Window framing, windows and service doors can now be installed.

When installing the door trims and cladding a minimal distance of 5 ½" must be maintained between the trim or cladding above the header and the trim or cladding on the door. This allows the door to open past 90 degrees without damaging either material. Cladding material with deeper than 1" profiles will require more distance. In these circumstance raise the building trims and cladding above the rough opening. Operate the door to verify that the trims and cladding will not collide. (See Typical Header Detail drawing)

The door bottom weatherstripping has closeouts on each end of the door. After door cladding is complete and the concrete is installed adjust to the closeout is necessary. Loosen screws on end closeout and adjust down to seal corners of door opening.

Seal the door frame to building jamb materials with a color matching sealant.

PowerLift Hydraulic Doors are fabricated with the anticipation that the door will be insulated and completed with a liner panel. No additional door modifications are required if this application is undertaken in the future.

Wainscoting

If wainscoting is scheduled on wood skeleton doors, the bottom of the lowest girt will be the top of the wainscot height from the finished floor. A 2x framing member is fastened vertically under the girt in the field by the builder. This results in 5" of fastening space for the wainscot and trims. On all steel skeleton doors, builders will supply any additional framing for wainscot application.

Wiring Connections

Both the pump and the remote control option can be wired by the same power supply. A 220v 30 amp breaker is required. All wiring is completed using the color coded wiring located in the pump switch box. (See Typical Electrical Connections drawing)

ELECTRICAL WIRING SHALL BE INSTALLED BY AN ELECTRICAL CONTRACTOR AND MEET FEDERAL, STATE AND LOCAL CODES.

Operating the door temporarily until permanent power is provided.

READ AND FOLLOW ALL SAFETY INSTRUCTIONS

The door is provided with pioneer type hydraulic nipples. These are located on the hydraulic lines directly above the locking valve. Tractors or other hydraulic equipment can operate the door using these connections. Hydraulic connections should be left attached for the entire door cycle to prevent pressure buildup.

If a generator must be used to supply temporary power for door operation, wiring, connections and power must be of adequate size. Do NOT starve the pump unit of electrical power. This will adversely affect the lifetime of the power unit and void the warranty. **Only use a generator that can provide 10,000 watts.** PowerLift Hydraulic Doors cannot be responsible for field conditions or temporary connections associated with temporary generators.

Suggested Framing Requirements

DUE TO FIELD CONDITIONS AND VARYING BUILDING PRACTICES POWERLIFT HYDRAULIC DOORS CAN ONLY MAKE RECOMMENDATIONS BASED UPON PAST EXPERIENCE. THE BUILDING SUPPLIER IS RESPONSIBLE FOR INCORPORATING ANY REACTIONS OR STRESSES IMPOSED BY POWERLIFT HYDRAULIC DOORS INTO THE BUILDING DESIGN. THE FINAL BUILDING STRUCTURE'S INTEGRITY IS THE RESPONSIBILITY OF THE BUILDING SUPPLIER.

Concrete Buildings:

Side Jamb: Minimum of 8" wide poured walls and 10" minimum for block walls with concrete and rebar core, full length to the foundation. Jamb material shall run the entire height of the wall from foundation to roof main framing. Provide diagonal bracing (45 degrees) at the

vertical jamb at the top of the door opening to roofing members. Install a vertical jamb molding to finish the jamb opening if desired.

Door post frame will be securely fastened with concrete bolts every 30" up the vertical jamb.

Header:

Concrete header: needs to be a Minimum of 8" wide poured walls and 10" minimum for block walls with concrete and rebar core.

Steel Header: Minimum single 8" wide, full header length 10 gauge c-channel or flanged beam securely fastened to side vertical concrete walls and provide diagonal bracing from header top to roofing members every hinge location or as specified by the building supplier. Maximum horizontal header deflection is 1". On 20' high doors, a diagonal from the upper cylinder mount is also recommended. Recommended diagonal bracing angle is 45 degrees.

Wood Header: Minimum 2 plies of 2x wood framing (3" thick) to a height of 8" from the bottom of the header opening. Recommended diagonal bracing angle is 45 degrees. Install diagonal framing from the header to the top of the next rafter (possible two rafter spaces to maintain recommended 45 degree angle). Provide diagonal bracing at a minimum of each hinge location and at the upper cylinder mount on 20' high doors.

Windows:

Windows can be installed in our doors. The window type selected is restricted to awning, fixed or sliding. The recommended rough opening or total size can be no larger than 5' wide or 4' high with no individual pane of glass being larger than 9 square feet (width multiplied by height). Recommended window mounting is by continuous molded or permanently attached window nail flange lapping the rough opening at least 1" at each edge and permanently fastened per manufactures instructions. All windows shall be installed per applicable building codes. Window supplier is responsible for: (a) providing windows of the correct glazing type, (b) sufficient framing and track depth so windows remain intact for door movement or varying horizontal positions, (c) installation of windows per manufacturer's instructions and (d) warranty for installation conditions. Due to varying conditions, PowerLift Hydraulic Doors cannot be held liable for any conditions or circumstances resulting from window installation.

Cane Bolts:

On larger width doors, cane bolts may be added to the inside of the truss near the center of the door. While the PowerLift door can withstand significant wind loads, the use of cane bolts adds additional strength at the door truss location. If severe or abnormal weather is anticipated the cane bolt can be engaged by lowering the bolt into a hole in the floor slab. This procedure may aid in preventing unwanted building or door damage. Under normal weather conditions the cane bolt may be left in the raised or unengaged position.

Never operate the door when the cane bolt is in the engaged or lowered position.



Typical Concrete Header Detail

Concrete building header, typically 8" to 12" thick pre-cast or masonry block with cement and rebar core

OUTSIDE OF BUILDING

Metal Sheeting
Optional


INSIDE OF BUILDING

Concrete anchor bolt located at least 5" up from top of frame header.

NOTES: Rubber weather-stripping **TO BE INSTALLED BY OTHERS** prior to gable sheeting. Weather-stripping to be placed over door trim and under building trim and sheeting.

Wedge or epoxy concrete anchor bolts through flat tab; tabs welded onto frame header.

Door trim and sheeting to be 5 1/2" down from the bottom of header for 1" profiles. Verify dimensions for thicker profiles. Weather-stripping over trims and sheeting. Seal top to prevent water penetration.






Typical Wood Header Detail

OUTSIDE
OF
BUILDING

INSIDE OF
BUILDING

Verify header requirements and wall construction with building supplier.

Install diagonal bracing as required, minimum one at each hinge.



Drip edge, lowest point above flush with header

NOTES: Rubber weather-stripping **TO BE INSTALLED BY OTHERS** prior to gable sheeting. Weather-stripping to be placed over door trim and under building trim and sheeting.

Door trim and sheeting to be 5 1/2" down from the bottom of header for 1" profiles. Verify dimensions for thicker profiles. Weather-stripping over trims and sheeting. Seal top to prevent water penetration.

Metal Sheeting

Trusses/Blocking

3" Lag through metal angle

5 x 5 Frame Tube Header

5 x 2 Door Tube Header

Nailer

J-Channel


5 x 3 Door Leg Post

5 x 3 Frame Tube Post

Metal Sheeting




Typical I-Beam Building Header Detail







Typical Concrete Building Side Jamb Detail



Typical Inside Mount Threshold with Existing Concrete




Typical Inside Mount Threshold with New Concrete






Typical Electrical Connections

Typical Motor Power Connections



Switch Control box

Typical Remote Control Electrical Connections



IF NO BLUE WIRE IS PROVIDED IN THE MOTOR
THE REMOTE CONTROL BLUE WIRE MUST BE CAPPED